

# Drywall Preparation Guidelines

- Framing must be completed, including all blocking!
- Clean room
- Map out pot lights (exactly!) & access hatch locations
- Holes in existing drywall must be closed up (drywalled) unless other arrangements have been made.
- We are responsible for protecting clients property (plastic/dropcloth/runners)
- Drywall scraps have to be hauled away by us unless we have dumpster onsite. Left in one pile (basement or garage)
- Need one working receptacle (they supply lights)
- All details have to be confirmed in advance. We need no confusion between sub-contractor/customer or our w/o.
- Leave small amounts of framing material behind

## Framing

- Inside corner studs have to be secured together in 3 spots
- Every inside corner leg bulkhead/ceiling, bulkhead/wall needs to have backer, even with floating corners
- All blocking must be placed every 2 ft.  
*4' walls important*
- If door stud is right at wall intersection it has to be secured to wall
- Ceiling needs to be cleared of:
  - Protruding bridging/blocks
  - Nails/screws
  - Joist hangers
  - Register covers